

00006

EPA Region 5 Records Ctr.



247971

SITE ASSESSMENT REPORT
FOR
DAVID CHEMICAL
CHICAGO, COOK COUNTY, ILLINOIS
TDD#: T05-9405-010
PAN#: EIL0838SAA



ecology and environment, inc.

International Specialists in the Environment

SITE ASSESSMENT REPORT
FOR
DAVID CHEMICAL
CHICAGO, COOK COUNTY, ILLINOIS
TDD#: T05-9405-010
PAN#: EIL0838SAA

JULY 11, 1994

Prepared By: Sally J. Jones Date: 7/11/94
Reviewed By: Michelle L. Gaster Date: 7/11/94
Approved By: John M. Zilly Date: 7/11/94



ecology and environment, inc.

111 WEST JACKSON BLVD., CHICAGO, ILLINOIS 60604, TEL. 312-663-9415

International Specialists in the Environment

recycled paper

TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
LIST OF FIGURES.....	ii
LIST OF TABLES.....	iii
LIST OF ATTACHMENTS.....	iv
1.0 INTRODUCTION.....	1
2.0 SITE DESCRIPTION.....	1
3.0 SITE BACKGROUND.....	1
4.0 SITE ASSESSMENT.....	4
5.0 ANALYTICAL RESULTS.....	7
6.0 THREATS TO HUMAN HEALTH AND THE ENVIRONMENT.....	14
7.0 SUMMARY.....	16

LIST OF FIGURES

<u>Figure</u>	<u>Page</u>
1 -- SITE LOCATION.....	2
2 -- SITE FEATURES.....	3
3 -- SITE SKETCH.....	6

LIST OF TABLES

<u>Table</u>	<u>Page</u>
1 -- TOTAL RCRA METALS ANALYTICAL RESULTS.....	8
2 -- TCLP METALS ANALYTICAL RESULTS.....	9
3 -- pH AND TOTAL CYANIDE ANALYTICAL RESULTS (SOLIDS).....	10
4 -- pH AND FLASHPOINT ANALYTICAL RESULTS (LIQUIDS).....	11
5 -- SEMI-VOLATILE AND ACID COMPOUND ANALYTICAL RESULTS....	12
6 -- VOLATILE AND F-LISTED ALCOHOL ANALYTICAL RESULTS.....	13

LIST OF ATTACHMENTS

Attachment

- A -- PHOTODOCUMENTATION
- B -- DRUM AND SAMPLE LOGS
- C -- CHAIN OF CUSTODY FORMS
- D -- COMMERCIAL LABORATORY ANALYTICAL RESULTS

1.0 INTRODUCTION



On May 17, 1994, the United States Environmental Protection Agency (U.S. EPA) tasked the Ecology and Environment, Inc. (E & E) Technical Assistance Team (TAT) under Technical Directive Document (TDD) T05-9405-010 to perform a site assessment at the David Chemical Site located in Chicago, Cook County, Illinois. The TAT assisted the U.S. EPA On-Scene Coordinator (OSC) with air monitoring, sample collection, and documentation of events and site conditions during the assessment. The assessment was conducted on May 27, 1994, to evaluate the threats to human health and the environment posed by the site.

2.0 SITE DESCRIPTION

The David Chemical (DC) site is an active chemical manufacturing and storage facility located at 4650 Fifth Avenue in Chicago, Cook County, Illinois (latitude 41°51'30", longitude 87°46'30"). Refer to Figure 1 for site location. The site consists of a main building which houses approximately 300 drums and small containers. The DC site is situated in a mixed residential/commercial area with Fifth Avenue defining the site's south boundary (see Figure 2). A railroad yard is located to the south across Fifth Avenue. The site is bordered to the west by Kilpatrick Avenue, to the north by G.F. Structure, and to the east by Joe's Drums. An warehouse building is located to the west across Kilpatrick Avenue. An easement directly adjacent to the north side of the site separates David Chemical and G.F. Structure. G.F. Structure also utilizes a fenced area adjacent to the west side of David Chemical for the storage of aluminum barricade material. A residential neighborhood is located approximately 1 block northwest of the site on Arthington Street and Sumner Elementary school is located 3 blocks to the northeast.

3.0 SITE BACKGROUND


The DC site is currently owned and operated by a private citizen. According to the owner, site operations began in 1987 and included the manufacturing of cleaning agents and detergents for sale and distribution to plating facilities, automatic car wash operators and portable toilet companies. DC utilized sodium bisulfate, proprietary chromic acid, chlorinated compounds (mostly water), and industrial dyes and perfumes in the cleaning agent manufacturing process. The proprietary chromic acid was obtained from Precision Chrome, an electroplating facility located in Fox Lake, Illinois. The cleaning agent manufacturing process was discontinued in 1993; however, DC continues to manufacture detergents on-site. Phosphates, bleach, and sodium nitrate are utilized in the detergent manufacturing process.



ecology and environment, Inc.
Technical Assistance Team
Region V

111 W. Jackson Blvd., Chicago, Illinois 60604

TITLE	Site Location Map	FIGURE #	1
SITE	David Chemical	SCALE	not to scale
CITY	Chicago	STATE	Illinois
SOURCE	E & E, Inc.	PAN	EIL0838SAA
		DATE	5/25/94
		REVISED	



Fluorboric acid is also reportedly used to adjust the pH of the products.

In September 1993, the Illinois Environmental Protection Agency (IEPA) conducted a site investigation at the DC site. The IEPA first learned about the site while investigating Precision Chrome, and subsequently discovered waste was shipped to and stored at David Chemical. The IEPA completed a site reconnaissance and sampling activities at the site. The IEPA reportedly observed several inches of free liquids on the floor inside the building which were leaching out from under a garage door onto Fifth Avenue. In addition, label information on numerous drums indicated hazardous substances were being stored in the building.

The IEPA collected samples from various drums and standing water on the floor. Analytical results from these samples indicated toxicity characteristic leaching procedure (TCLP) chromium concentrations of 490,000 mg/l in the drums of proprietary chromic acid and 4,000 mg/l in material on the floor respectively. A sample was also collected from the material leaching out from under the garage. Analytical results revealed TCLP chromium at 880 mg/l. In addition, IEPA reported that the pH of the floor sample was less than two standard units. Comprehensive analytical results from IEPA sampling events were unavailable at the time this report was prepared.

In April 1994, the IEPA contacted the U.S. EPA Emergency and Enforcement Branch (EERB) to report David Chemical for illegal storage and use of hazardous substances and materials. The State of Illinois is currently pursuing legal action against DC for violations under the Resource Conservation and Recovery Act (RCRA). David Chemical does not hold a RCRA permit.

4.0 SITE ASSESSMENT

At 0830 hours on May 27, 1994, U.S. EPA On Scene Coordinator (OSC) Pete Guria, and E & E TAT members (TATms) Sally Imes, Michelle Jaster, and Mike Mangini arrived at the DC site in Chicago, Illinois. Upon arrival, the OSC and TATms were greeted by the site owner. The OSC and TATms conducted an on-site safety meeting and prepared to enter the building for a site walkthrough.



At 0900 hours TATms Imes and Jaster entered the building in Level B personal protective equipment to perform preliminary air monitoring. TATm Mangini remained at the door of the building as a backup. Real-time air monitoring was conducted for oxygen, lower explosive limit (LEL), hydrogen cyanide (HCN), organic vapors and radioactive materials. Oxygen level and LEL were measured utilizing a MSA 260 combustible gas indicator (CGI). A

chemical specific (HCN) monitox gas detector and Photovac Microtip photoionization detector (PID) were utilized to detect HCN and organic vapors respectively. TATms also conducted a radiation survey for gamma rays utilizing a Victoreen Thyac III. All instruments were calibrated according to manufacturer recommendations before entering the building. Organic vapor readings were detected between 4.5 and 12.6 parts per million (ppm) in the breathing zone. In addition, monitoring was conducted for organic vapors at the bung opening of a drum labeled mineral spirits. Microtip readings peaked at 2,500 ppm. No other readings above background were detected on any other air monitoring equipment.

After evaluating real-time air monitoring results, TATms Imes and Jaster, and OSC Guria re-entered the building in Level C personal protection to document chemical information and site observations, and to determine sampling locations. The OSC and the TATms observed approximately 300 drums and small containers stored within the site building. Drums were stored on wooden pallets on top of each other, some stacked three and four high. A majority of these drums were staged along the perimeter walls of the building (see Figure 3). According to the owner, and drum labels documented during the assessment, the following chemicals were present on-site: fluorboric acid, proprietary chromic acid, calcium hypochlorite, sodium hydroxide, caustic beads, acetic acid, gluconic acid, hydrofluoric acid, glycol ether, potassium nitrate, and sodium xylene sulfonate. The site owner informed the OSC the drums were staged according to hazard classes. However, the TAT observed a pallet containing caustic beads (corrosive material) stored in the western portion of the building with a 5 gallon can containing isopropyl alcohol (flammable liquid) on the floor next to the pallet (see Attachment A - photodocumentation).

Wood pallets, miscellaneous drums and small containers, several forklifts and various debris were scattered throughout the building. At the time of the site assessment, several holes in the roof were observed. One hole was located in the northwest portion of the roof and was approximately 20 feet by 20 feet in size. In addition, the hole was directly over drums containing mineral spirits and hydrofluoric acid. Standing water was also observed in various areas on the floor throughout the building. TATms tested the pH of the standing water in the northwest section of the building near drums containing caustic materials. Results revealed a pH greater than 10.0 standard units. After determining appropriate sample locations, the OSC and TATms exited the building to prepare for sampling.

At 1030 hours TATm Jaster and Mangini entered the building to conduct sampling activities in Level B personal protection equipment. A total of 7 samples were collected from drums (D001 thru D003), buckets (BK-01), plastic bags (BG-01), DC detergent



ecology and environment, Inc.
Technical Assistance Team
Region V

111 W. Jackson Blvd., Chicago, Illinois 60604

TITLE Site Features Map - Detail		FIGURE # 3
SITE David Chemical		SCALE not to scale
CITY Chicago	STATE Illinois	PAN EIL0838SAA
SOURCE E & E		DATE 5/25/94
		REVISED

product (PR-01), and material present on the floor (FS-01). Drum and sample logs were completed for all samples collected (see Attachment B). General hazardous categorization testing was conducted on all samples in order to assist in determining analytical parameters to be run on each individual sample. All samples were collected and packaged in accordance with U.S. EPA standard operating procedures. Upon completion of sampling, the OSC and TATms departed the site at 1205 hours.

Samples designated FS-01 and D002 were shipped via Federal Express according to Department of Transportation (DOT) regulations to NET Midwest Laboratory in Bartlett, Illinois. As requested by the OSC, sample FS-01 was analyzed for semi-volatile organic compounds, and sample D002 was analyzed for volatile and semi-volatile organic compounds, as well as F listed alcohol compounds. The remaining samples were packaged appropriately and refrigerated, prior to analysis by IEA Laboratories (IEA), Schaumburg, Illinois. IEA provided carrier service on May 31, 1994, and the samples were hand-delivered to the laboratory for total and TCLP metals (8 RCRA), flashpoint, total and reactive cyanide and sulfide, and pH analysis. Specific analytical parameters were assigned for each sample (see Attachment C -- Chains of Custody). All samples were analyzed under Analytical TDD# T05-9405-807. QA Level II data with a 7 calendar day verbal turnaround time, and 14 calendar day hard copy was requested from both laboratories.

5.0 ANALYTICAL RESULTS

Analytical results are presented in Tables 1-6. Elevated levels of total chromium were detected in samples D003 and PR-01 at 120,000 and 24,000 parts per million (ppm) respectively. TCLP analytical results indicated chromium levels elevated above the regulatory limit of 5 mg/l in samples BK-01 and FS-01. TCLP chromium levels in these floor sludge samples were detected at 630 and 11 mg/l respectively. Elevated semi-volatile organic compounds, specifically polyaromatic hydrocarbons such as fluoranthene, pyrene, and phenanthrene, were also detected in floor sludge sample FS-01 at levels as high as 4.9 ppm. A total cyanide level of 6 ppm was detected in sample BK-01. Analytical results indicated that samples D001 and D003 are corrosive liquids with pH values of < 1.0 standard units. Analytical results also indicated elevated levels of volatile organic compounds, semi-volatile organic compounds, and F-listed alcohols were detected in sample D002. This sample contained 12,200 ppm methylene chloride, 265 ppm 1,1,1-trichloroethane, 165 ppm toluene, and 138 ppm total xylenes. Refer to Attachment D for complete commercial laboratory analytical results.

TABLE 1**TOTAL RCRA METALS ANALYTICAL RESULTS
SAMPLES COLLECTED - MAY 27, 1994****DAVID CHEMICAL
CHICAGO, ILLINOIS**

PARAMETERS	SAMPLE ID NUMBERS		
	D001	D003	PR-01
TOTAL RCRA METALS	RESULTS IN (ppm)		
Arsenic	0.57	12	<0.5
Barium	0.42	<0.5	<0.5
Cadmium	0.0052	<0.25	<0.05
Chromium	0.33	120,000	24,000
Lead	0.5	<2.5	<0.5
Mercury	0.0072	<0.002	<0.002
Selenium	<0.1	<6.0	<6.0
Silver	<0.01	<0.5	0.14

NOTE: Total Metals Analysis performed by: IEA Laboratories
Schaumburg, Illinois.

TABLE 2**TCLP METALS ANALYTICAL RESULTS
SAMPLES COLLECTED - MAY 27, 1994****DAVID CHEMICAL
CHICAGO, ILLINOIS**

PARAMETERS	SAMPLE ID NUMBERS		
	BK-01	BG-01	FS-01
TCLP METALS (Reg. Limit)	RESULTS IN (mg/l)		
Arsenic (5)	0.78	<0.1	<0.1
Barium (100)	0.54	0.43	0.59
Cadmium (1)	0.0073	<0.005	0.033
Chromium (5)	630	<0.01	11
Lead (5)	0.084	<0.05	<0.05
Mercury (0.2)	<0.0002	<0.0002	<0.0002
Selenium (1)	<0.1	<0.1	<0.1
Silver (5)	<0.01	<0.01	<0.01

NOTE: All analytical results detected above regulatory limits are shaded.

TCLP Metals Analysis performed by: IEA Laboratories
Schaumburg, Illinois.

TABLE 3

pH and TOTAL CYANIDE ANALYTICAL RESULTS
SOLID SAMPLES COLLECTED - MAY 27, 1994

DAVID CHEMICAL
CHICAGO, ILLINOIS

PARAMETERS	SAMPLE ID NUMBERS		
	BK-01	BG-01	FS-01
pH (standard units)	9.9	3.2	7.7
TOTAL CYANIDE (ppm)	6.0	NR	NR

NOTE: NR -- Analytical parameter not run on this specific sample.

Sample FS-01 also analyzed for Reactive Cyanide, Total Sulfide, and Reactive Sulfide. None of these parameters were detected above the appropriate Practical Quantitation Limit (PQL).

All analyses performed by: IEA Laboratories
Schaumburg, Illinois.

TABLE 4

**pH and FLASHPOINT ANALYTICAL RESULTS
LIQUID SAMPLES COLLECTED - MAY 27, 1994**

**DAVID CHEMICAL
CHICAGO, ILLINOIS**

PARAMETERS	SAMPLE ID NUMBERS			
	D001	D003	PK-01	D002
pH (standard units)	<1.0	<1.0	3.5	NR
FLASHPOINT	NR	NR	NR	115°F

NOTE: NR -- Analytical parameter not run on this specific sample.

Sample D003 also analyzed for Total and Reactive Cyanide, as well as Total and Reactive Sulfide. None of these parameters were detected above the appropriate Practical Quantitation Limit (PQL).

All analyses performed by: IEA Laboratories
Schaumburg, Illinois.

TABLE 5

SEMI-VOLATILE AND ACID COMPOUNDS ANALYTICAL RESULTS
SAMPLES COLLECTED - MAY 27, 1994DAVID CHEMICAL
CHICAGO, ILLINOIS

PARAMETERS	SAMPLE ID NUMBER	
SEMI-VOLATILES (results in ppm)	FS-01	D002
Acenaphthene	0.36	<100 U
Anthracene	0.81	<100 U
Benzo(a)anthracene	2.0	<100 U
Benzo(b)fluoranthene	1.9	<100 U
Benzo(k)fluoranthene	1.4	<100 U
Benzo(g,h,i)perylene	1.1	<100 U
Benzo(a)pyrene	1.7	<100 U
Benzyl butyl phthalate	0.4	<100 U
Bis(2-ethylhexyl)phthalate	3.04	<100 U
Chrysene	2.2	<100 U
Dibenzo(a,h)anthracene	0.53	<100 U
Di-n-butyl phthalate	0.74	<100 U
2,6-Dinitrotoluene	<0.32 U	100
Fluoranthene	4.9	<100 U
Fluorene	0.42	<100 U
Naphthalene	<0.32 U	120
Indeno(1,2,3-cd)pyrene	1.1	<100 U
Phenanthrene	2.27	380
Pyrene	3.6	<100 U
ACID COMPOUNDS		
Phenol	NR	160

NOTE: NR -- Analytical parameter not run on this specific sample.

U -- Analyte was not detected above the level of the associated number, the quantitation limit.

All samples were analyzed by NET Laboratories, Bartlett, Illinois

TABLE 6**VOLATILE AND F-LISTED ALCOHOL ANALYTICAL RESULTS
SAMPLES COLLECTED - MAY 27, 1994****DAVID CHEMICAL
CHICAGO, ILLINOIS**

PARAMETER	SAMPLE ID #
VOLATILE COMPOUNDS (results in ppm)	D002
1,1-Dichloroethane	5.5
Ethyl benzene	21.0
Methylene chloride	12,200 *
Toluene	165
1,1,1-Trichloroethane	265
Trichloroethene	9.5
Total Xylenes	138
F-LISTED ALCOHOLS (results in ppm)	
2-Ethoxyethanol	15.6
Methanol	1.2

NOTE: * -- Parameter analysis performed at a 20,000 x dilution.

Sample was analyzed by: NET Laboratories
Bartlett, Illinois.

6.0 THREATS TO HUMAN HEALTH AND THE ENVIRONMENT

Conditions observed during the U.S. EPA investigation of the DC site that constitute a threat to human health and the environment and may be used to determine the appropriateness of a removal action as outlined in Section 300.415(b)(2) of the National Contingency Plan (NCP) included:

- a) Actual or potential exposure of nearby human populations, animals, or food chains from hazardous substances or pollutants or contaminants;

Potential exposure of nearby populations to hazardous materials exists at the DC site. Analytical results of floor sludge samples collected at the site indicated levels of TCLP chromium above the regulatory limit of 5 mg/l. Chromic acid is a human carcinogen that can be absorbed through all routes of exposure, resulting in severe nose and throat irritation, as well as stomach or kidney problems. Analytical results also indicated the presence of other corrosive acids with pH values less than 1.0 standard units in drum samples D001 and D003. Contact with strong acids can result in severe skin or eye burns, and irritation to the nose, throat, and respiratory tract. In addition, total cyanide levels of 6 ppm were detected in a bucket sample (BK-01) collected from floor sweepings. The presence of acidic and cyanide compounds on the floor could potentially result in the formation of hydrogen cyanide gas, if mixing were to occur. Hydrogen cyanide is a poisonous gas with a low threshold limit value (TLV) of 10 ppm. Analytical results have also indicated the presence of a wide variety of volatile organic compounds, including methylene chloride (12,200 ppm), ethyl benzene (21 ppm), and xylenes (138 ppm) stored in drums at the site. These hazardous substances pose inhalation, ingestion, and direct contact hazards which can potentially result in irritation to the respiratory tract, eyes, and skin. The potential exists for nearby populations to come into contact with these volatile organic compounds, as well as the other hazardous substances previously discussed. The current owner admitted to numerous episodes of vandalism and trespassing at the site. Populations that could potentially be exposed to the hazardous chemicals on-site include workers of adjacent facilities, residents located one block to the northwest, and children from an elementary school located three blocks to the northeast.

- b) Hazardous substances or pollutants or contaminants in drums, barrels, tanks, or other bulk storage containers, that may pose a threat of release;

Over 300 drums and miscellaneous small containers (5 gallon or less) are stored at the DC site. Many of these drums are stacked two and three high in an overcrowded warehouse area. Analytical results have indicated that many of these drums contain corrosive

acids with pHs less than 1.0 ppm. The potential exists for the contents of the drums to come into contact with incompatible floor sludges, resulting in a release of hazardous liquids or gases. Analytical results of floor sludges have indicated the presence of elevated levels of TCLP chromium at 11 mg/l, total cyanide at 6 ppm, and various semi-volatile compounds, including fluoranthene, pyrene, and bis(2-ethylhexyl)phthalate at 4.9 ppm, 3.6 ppm, and 3.04 ppm respectively. In addition, the roof of the facility has numerous holes, resulting in the continued exposure of drums and floor sludges to the elements. The IEPA has documented leaching of materials from inside the facility to the street underneath a garage door. IEPA analytical results have indicated that the floor sludges contain 4,000 mg/l TCLP chromium and have a pH less than 2 standard units. Numerous areas of pooled liquid were noted throughout the building during the U.S. EPA site assessment, with one area containing liquid with a pH greater than 10 standard units. Air monitoring conducted inside the building during the assessment indicated elevated levels of organic vapors in the breathing zone.

- c) Weather conditions that may cause hazardous substances or pollutants or contaminants to migrate or be released;

The roof of the facility contains several large holes, allowing precipitation to enter the building. According to IEPA personnel, this has resulted in the migration of floor sludges containing elevated levels of hazardous substances outside of the building to the street. Continued exposure of the drums and containers to precipitation could result in the deterioration of the condition of the drums and the leaking of their contents. This could potentially result in the mixing and migration of a wide variety of incompatible materials such as cyanide, strong acids, oxidizers such as chromic acid, caustic liquids such as calcium hypochlorite and sodium hydroxide, and volatile organic compounds such as methylene chloride and xylene, posing a threat to nearby populations.

- d) Threat of fire or explosion;

Analytical results of a sample collected from drum D002 indicated a flashpoint of 115°F which is below the RCRA limit for ignitability of 140°F. In addition numerous drums located throughout the building were labeled as flammable material. In some cases, these drums with flammable contents were stored directly adjacent to corrosive materials, creating a fire potential. Due to the incompatible chemical composition of corrosive and flammable materials, mixing may cause spontaneous combustion to occur ultimately creating an ignition source. Elevated organic vapor levels were noted during air monitoring of several drums and also in the breathing zone within the site. Repeated instances of trespassing and vandalism at the facility, coupled with the presence of numerous drums of incompatible and

flammable materials, could potentially result in a fire at the site. A residential community is located only one block to the northwest of the site. As a result of a fire on-site, nearby populations would face inhalation, ingestion, and direct contact threats from the hazardous materials stored within the facility.

7.0 SUMMARY

A removal action is warranted at the DC site based on the above factors as well as the on-site storage of over 300 drums and small containers containing elevated levels of TCLP chromium, corrosive acids, and volatile organic compounds. The continued exposure of drummed materials and floor sludges to precipitation events through holes in the building's roof could potentially result in additional migration of hazardous substances to the street outside the facility. In addition, there is a history of trespassing and vandalism at the site, and further instances could result in the release of hazardous substances to nearby populations and the environment.

ATTACHMENT A
PHOTODOCUMENTATION




SITE NAME: DAVID CHEMICAL
TDD: T05-9405-010

DATE: 5/27/94
TIME: 0830 HOURS

PHOTOGRAPHER: SALLY IMES

DIRECTION: NORTHWEST

SUBJECT: SOUTH SIDE OF BUILDING WHICH
HOUSES DAVID CHEMICAL. DAVID
CHEMICAL MANUFACTURES DETERGENTS
UTILIZED BY CAR WASHES AND
PORTABLE TOILET COMPANIES.




SITE NAME: DAVID CHEMICAL
TDD: T05-9405-010

DATE: 5/27/94
TIME: 0830 HOURS

PHOTOGRAPHER: SALLY IMES

DIRECTION: EAST

SUBJECT: WEST SIDE OF DAVID CHEMICAL.
FENCED IN AREA IS UTILIZED BY G.F.
STRUCTURES CORP. TO STORE ALUMINUM
BARRICADE MATERIAL.




SITE NAME: DAVID CHEMICAL
TDD: T05-9405-010

DATE: 5/27/94
TIME: 0835 HOURS

PHOTOGRAPHER: SALLY IMES

DIRECTION: SOUTHEAST

SUBJECT: NORTH SIDE OF FENCED AREA WHERE
GATE TO ACCESS STORAGE AREA IS
LOCATED.



SITE NAME: DAVID CHEMICAL
TDD: T05-9405-010

DATE: 5/27/94
TIME: 0835 HOURS

PHOTOGRAPHER: SALLY IMES

DIRECTION: SOUTHEAST

SUBJECT: SIGN POSTED ON GATE BY G.F.
STRUCTURE AS MEANS OF SECURITY.



TE NAME: DAVID CHEMICAL
D: T05-9405-010

TE: 5/27/94
ME: 0835 HOURS

OTOGRAPHER: SALLY IMES

RECTION: WEST

BJECT: EASEMENT DIRECTLY ADJACENT TO THE
NORTH SIDE OF DAVID CHEMICAL SITE.
EMPTY DRUMS STORED BELONG TO DAVID
CHEMICAL.



SITE NAME: DAVID CHEMICAL
TDD: T05-9405-010

DATE: 5/27/94
TIME: 1140 HOURS

PHOTOGRAPHER: SALLY IMES

DIRECTION: SOUTHWEST

SUBJECT: G.F. STRUCTURE CORP. LOCATED NORTH
OF DAVID CHEMICAL. G.F.
MANUFACTURES BARRICADES FOR THE
CITY OF CHICAGO.



SITE NAME: DAVID CHEMICAL
 TDD: T05-9405-010

 DATE: 5/27/94
 TIME: 1130 HOURS

 PHOTOGRAPHER: PETE GURIA

 DIRECTION: WEST

 SUBJECT: RAIL YARD LOCATED SOUTH OF DAVID
 CHEMICAL ACROSS 5TH STREET.





SITE NAME: DAVID CHEMICAL
 TDD: T05-9405-010

 DATE: 5/27/94
 TIME: 1135 HOURS

 PHOTOGRAPHER: PETE GURIA

 DIRECTION: EAST

 SUBJECT: JOE'S DRUM; FACILITY IS LOCATED
 WEST OF SITE.



TE NAME: DAVID CHEMICAL
D: T05-9405-010

TE: 5/27/94
ME: 1135 HOURS

OTOGRAPHER: PETE GURIA

RECTION: NORTHWEST

BJECT: VIEW OF DAVID CHEMICAL SITE
LOCATED AT 4650 5TH STREET,
CHICAGO, ILLINOIS

SITE NAME: DAVID CHEMICAL
TDD: T05-9405-010

DATE: 5/27/94
TIME: 0900 HOURS

PHOTOGRAPHER: SALLY IMES

DIRECTION: SOUTHWEST

SUBJECT: SOUTHWEST CORNER INSIDE BUILDING.
NOTE: SCATTERED DEBRIS.



SITE NAME: DAVID CHEMICAL
TDD: T05-9405-010

DATE: 5/27/94
TIME: 0900 HOURS

PHOTOGRAPHER: SALLY IMES

DIRECTION: SOUTH

SUBJECT: 5-GALLON BUCKETS, CONTAINING
CLEANING AGENT, ALONG SOUTH WALL.



SITE NAME: DAVID CHEMICAL
TDD: T05-9405-010

DATE: 5/27/94
TIME: 0905 HOURS

PHOTOGRAPHER: SALLY IMES

DIRECTION: EAST

SUBJECT: SOUTHEAST CORNER INSIDE OF
BUILDING. DRUMS WITH UNKNOWN
CONTENTS STACKED THREE HIGH.



TE NAME: DAVID CHEMICAL
D: T05-9405-010

TE: 5/27/94
ME: 0905 HOURS

OTOGRAPHER: SALLY IMES

RECTION: EAST

BJECT: DRUMS AND DEBRIS ALONG EAST WALL
OF BUILDING.



SITE NAME: DAVID CHEMICAL
TDD: T05-9405-010

DATE: 5/27/94
TIME: 0905 HOURS

PHOTOGRAPHER: SALLY IMES

DIRECTION: NORTHEAST

SUBJECT: DRUMS, 5-GALLON BUCKETS, AND
DEBRIS ALONG EAST WALL OF
BUILDING. NOTE: SEVERAL BOXES OF
EMPTY 1-GALLON BOTTLES UTILIZED TO
PACKAGE PRODUCT.



SITE NAME: DAVID CHEMICAL
TDD: T05-9405-010

DATE: 5/27/94
TIME: 0940 HOURS

PHOTOGRAPHER: SALLY IMES

DIRECTION: NORTHWEST

SUBJECT: BUCKET OF MATERIAL WHICH WAS
REMOVED FROM THE FLOOR BY THE PRP.
A SAMPLE WAS COLLECTED FROM THIS
MATERIAL.




SITE NAME: DAVID CHEMICAL
TDD: T05-9405-010

DATE: 5/27/94
TIME: 1015 HOURS

PHOTOGRAPHER: MICHELLE JASTER

DIRECTION: NORTH

SUBJECT: LARGE HOLES IN ROOF OF BUILDING.
NOTE: HOLE IS DIRECTLY OVER
BUCKETS AND DRUMS.



E NAME: DAVID CHEMICAL
: T05-9405-010

E: 5/27/94
E: 1015 HOURS

TOGRAPHER: MICHELLE JASTER

ECTION: NORTHWEST

JECT: DRUMS CONTAINING UNKNOWN MATERIAL
DIRECTLY BENEATH HOLE IN ROOF.

SITE NAME: DAVID CHEMICAL
TDD: T05-9405-010

DATE: 5/27/94
TIME: 1020 HOURS

PHOTOGRAPHER: MICHELLE JASTER

DIRECTION: EAST

SUBJECT: ROOF OF BUILDING CONTAINS SEVERAL
HOLES AND CEILING BEAMS APPEAR TO
BE IN DETERIORATING CONDITION.



SITE NAME: DAVID CHEMICAL
 TDD: T05-9405-010

DATE: 5/27/94
 TIME: 1000 HOURS

PHOTOGRAPHER: SALLY IMES

DIRECTION: SOUTHWEST

SUBJECT: PALLETS OF CAUSTIC SODA STORED
 NEXT TO A 5-GALLON CAN OF
 ISOPROPYL ALCOHOL.



SITE NAME: DAVID CHEMICAL
 TDD: T05-9405-010

DATE: 5/27/94
 TIME: 1005 HOURS

PHOTOGRAPHER: SALLY IMES

DIRECTION: NORTH

SUBJECT: DAVID CHEMICAL UTILIZED
 PROPRIETARY CHROMIC ACID TO
 MANUFACTURE CLEANING AGENT. NOT
 DRUMS ARE STACKED 3 ROWS HIGH, A
 STORED NEAR CALCIUM HYPOCHLORITE



SITE NAME: DAVID CHEMICAL
TDD: T05-9405-010

DATE: 5/27/94
TIME: 1005 HOURS

PHOTOGRAPHER: SALLY IMES

DIRECTION: EAST

SUBJECT: GLYCONIC ACID STORED IN NORTHEAST
CORNER OF BUILDING.




SITE NAME: DAVID CHEMICAL
TDD: T05-9405-010

DATE: 5/27/94
TIME: 1007 HOURS

PHOTOGRAPHER: SALLY IMES

DIRECTION: EAST

SUBJECT: DRUMS CONTAINING FLAMMABLE LIQUIDS
STORED ALONG EAST WALL.



SITE NAME: DAVID CHEMICAL
TDD: T05-9405-010

DATE: 5/27/94
TIME: 1040 HOURS

PHOTOGRAPHER: MICHELLE JASTER

DIRECTION: NORTHEAST

SUBJECT: SAMPLE D001 COLLECTED FROM A DRUM
SUSPECTED TO CONTAIN HYDROFLUORIC
ACID. pH WAS < 1.0.




SITE NAME: DAVID CHEMICAL
TDD: T05-9405-010

DATE: 5/27/94
TIME: 1045 HOURS

PHOTOGRAPHER: MICHELLE JASTER

DIRECTION: NORTHEAST

SUBJECT: SAMPLE D002 COLLECTED FROM MARKE
OIL CLEANER. MICROTIP READINGS
OBTAINED WERE APPROXIMATELY 600
PPM.




TE NAME: DAVID CHEMICAL
 D: T05-9405-010

 TE: 5/27/94
 ME: 1045 HOURS

 OTOGRAPHER: MICHELLE JASTER

 RECTION: NORTHEAST

 BJECT: DRUMS D001 AND D002 LOCATED IN
 NORTHWEST SECTION OF BUILDING
 BENEATH HOLE IN ROOF.



SITE NAME: DAVID CHEMICAL
 TDD: T05-9405-010

 DATE: 5/27/94
 TIME: 1050 HOURS

 PHOTOGRAPHER: MICHELLE JASTER

 DIRECTION: NORTHWEST

 SUBJECT: SAMPLE D003 COLLECTED FROM DRUM
 MARKED PROPRIETARY CHROMIC ACID.



SITE NAME: DAVID CHEMICAL
TDD: T05-9405-010

DATE: 5/27/94
TIME: 1105 HOURS

PHOTOGRAPHER: MICHELLE JASTER

DIRECTION: NORTH

SUBJECT: SAMPLE BG-01 COLLECTED FROM
MATERIAL STORED IN AN UNMARKED
BAG.




SITE NAME: DAVID CHEMICAL
TDD: T05-9405-010

DATE: 5/27/94
TIME: 1115 HOURS

PHOTOGRAPHER: MICHELLE JASTER

DIRECTION: WEST

SUBJECT: SAMPLE BK-01 COLLECTED FROM
5-GALLON BUCKET. PRP STATED
MATERIAL WAS REMOVED FROM THE
FLOOR AFTER A SPILL.




SITE NAME: DAVID CHEMICAL
ID: T05-9405-010

DATE: 5/27/94
TIME: 1120 HOURS

PHOTOGRAPHER: MICHELLE JASTER

DIRECTION: EAST

SUBJECT: SAMPLE FS-01 COLLECTED FROM FLOOR
SWEEPINGS ALONG EAST WALL NEAR
FLUOROBORIC AND GLACIAL ACETIC
ACID DRUMS.



SITE NAME: DAVID CHEMICAL
TDD: T05-9405-010

DATE: 5/27/94
TIME: 1120 HOURS

PHOTOGRAPHER: MICHELLE JASTER

DIRECTION: EAST

SUBJECT: CLOSE-UP OF FLOOR WHERE FS-01 WAS
COLLECTED.

ATTACHMENT B
DRUM AND SAMPLE LOGS

DRUM LOG FORM

DRUM NO. 5001

DAVID CHEMICAL SITE

DATE: 5/27/94 TIME: 1040

DRUM SIZE (GAL.): 5 30

55

OTHER poly (yellow)

QUANTITY: EMPTY 1/8 1/4 1/3 1/2 3/4 FULL

DRUM CONDITION: EXC. GOOD FAIR POOR

COMMENTS: _____

SAMPLE METHOD: DRUM THIEF TROWEL OTHER _____

CONTENTS: SOLID _____ IN. SEMI-SOLID _____ IN.

SLUDGE _____ IN. LIQUID _____ IN.

MARKINGS: corrosive sticker
marked hydrofluoric acid

COLOR: Clear

pH: _____

GRAIN SIZE: _____

ADDITIONAL COMMENTS: _____

NW corner of bldg
under hole in roof

D
R
U
M

DRUM LOG FORM

DRUM NO. 2000T

DAVID CHEMICAL SITE

DATE: 5/27/94 TIME: 1045

DRUM SIZE (GAL.): 5 30

55

OTHER poly (blue)

QUANTITY: EMPTY 1/8 1/4 1/3 1/2 3/4 FULL

DRUM CONDITION: EXC. GOOD FAIR POOR

COMMENTS: _____

SAMPLE METHOD: DRUM THIEF TROWEL OTHER _____

CONTENTS: SOLID _____ IN. SEMI-SOLID _____ IN.

SLUDGE _____ IN. LIQUID all IN.

MARKINGS: oil cleaner
PRP says its mineral spirits

COLOR: gold lig

pH: _____

GRAIN SIZE: _____

D
R
U
M

ADDITIONAL COMMENTS: _____

NW section of bldg to E of DCC
under hole in roof
~600 ppm or Ni only

DRUM LOG FORM

DRUM NO. D003

DAVID CHEMICAL SITE

DATE: 5/27/94 TIME: 1050

DRUM SIZE (GAL.): 5 30 55 OTHER poly (black)

QUANTITY: EMPTY 1/8 1/4 1/3 1/2 3/4 FULL

DRUM CONDITION: EXC. GOOD FAIR POOR

COMMENTS: _____

SAMPLE METHOD: DRUM THIEF TROWEL OTHER _____

CONTENTS: SOLID _____ IN. SEMI-SOLID _____ IN.
SLUDGE _____ IN. LIQUID fuel IN.

MARKINGS: proprietary chromic acid

COLOR: burnt orange

pH: ~2

GRAIN SIZE: _____

D
R
U
M

ADDITIONAL COMMENTS:
Neutral/NE portion of bldg
2 drums E of trailer

DRUM LOG FORM

DRUM NO. 127-102

DAVID CHEMICAL SITE

DATE: 5/27/94 TIME: 715

DRUM SIZE (GAL.): 5 30 55 OTHER Plastic Bag 2010

QUANTITY: EMPTY 1/8 1/4 1/3 1/2 3/4 (FULL)

DRUM CONDITION: EXC. GOOD FAIR (POOR

COMMENTS: Hole in bag

SAMPLE METHOD: DRUM THIEF TROWEL OTHER Shovel

CONTENTS:	(SOLID)	IN.	SEMI-SOLID	IN.
-----------	---------	-----	------------	-----

SLUDGE IN. LIQUID IN.

MARKINGS: no markings
PRP says caustic

COLOR: rust colored pellets

pH: _____

GRAIN SIZE:

ADDITIONAL COMMENTS:

NEUTRAL PORTION OF BLDG JUST W/ST TRAIL
ON TOP OF NUMEROUS 2016 BAGS
OF BLUE PET LBS

**D
R
U
M**

DRUM LOG FORM

DRUM NO. BK-01

DAVID CHEMICAL SITE

DATE: 5/27/94

TIME: 1115

DRUM SIZE (GAL.): 5 30 55 OTHER gal steel bucket

QUANTITY: EMPTY 1/8 1/4 1/3 1/2 3/4 FULL

DRUM CONDITION: EXC. GOOD FAIR POOR

COMMENTS: _____

SAMPLE METHOD: DRUM THIEF TROWEL OTHER SPOT

CONTENTS: SOLID IN. SEMI-SOLID IN.
SLUDGE IN. LIQUID IN.

MARKINGS: PPH says floor sweepings from around
chronic acid drums. spill cleaned w/ TSP

COLOR: yellow + white

pH: _____

GRAIN SIZE: _____

D
R
U
M

ADDITIONAL COMMENTS: NW corner of bldg just east
of garage door

DRUM LOG FORM

DRUM NO. PS-01

DAVID CHEMICAL SITE

DATE: 5/27/94

TIME: 1200

DRUM SIZE (GAL.): 5 30 55 OTHER N/A

QUANTITY: EMPTY 1/8 1/4 1/3 1/2 3/4 FULL

DRUM CONDITION: EXC. GOOD FAIR POOR

COMMENTS: _____

SAMPLE METHOD: DRUM THIEF TROWEL OTHER _____

CONTENTS: SOLID _____ IN. SEMI-SOLID _____ IN.

 SLUDGE _____ IN. LIQUID _____ IN.

MARKINGS: _____

COLOR: _____

pH: _____

GRAIN SIZE: _____

D
R
U
M

ADDITIONAL COMMENTS: _____

Floor sludge from along E wall
Brown, wet dirt

Near Glacial acid drums
NOT Phosphoric acid drums

DRUM LOG FORM

DRUM NO. PR-01

DAVID CHEMICAL SITE

DATE: 5/27/94

TIME: 1055

DRUM SIZE (GAL.): 5 30 55 OTHER 1 gallon

QUANTITY: EMPTY 1/8 1/4 1/3 1/2 3/4 FULL

DRUM CONDITION: EXC. GOOD FAIR POOR

COMMENTS: _____

SAMPLE METHOD: DRUM THIEF TROWEL OTHER _____

CONTENTS: SOLID _____ IN. SEMI-SOLID _____ IN.

 SLUDGE _____ IN. LIQUID ✓ IN.

MARKINGS: _____

COLOR: dk green

pH: _____

GRAIN SIZE: _____

D
R
U
M

ADDITIONAL COMMENTS: PEP product -

dk green in color

ATTACHMENT C
CHAIN OF CUSTODY FORMS

CHAIN OF CUSTODY RECORD

PROJ. NO. ZT 2054		PROJECT NAME TOS-9405-807			No. of CONTAINERS	Analysis: <i>PH</i> Total Metals - 8 EPCA Total Leachate Sulfate Total Leachate Cyanide Flashpoint TCLP Metals - 8 EPCA								TAG NUMBERS
SAMPLERS: (Print Name and Sign) Michelle L. Jaster Sally Innes <i>Sally Innes</i>														
STA. NO.	DATE	TIME	COMP.	GRAB	STATION LOCATION									
D001	5/27/94	1040		✓	Drum	1-3203	X	X						
D002		1045		✓	Drum	1-803					X		HNu readings > 600 ppm	
D003		1050		✓	Drum	1-3203	X	X	X	X				
PR-01		1055		✓	PRP Product	1-3203	X	X						
BK-01		1115		✓	Bucket - floor	1-3203	X					X		
BG-01		1105		✓	Bagged contents	1-3203	X					X		
FS-01		1130		✓	Floor Sludge	1-3203	X		X	X		X		
					Billing: Results to M.J. Ripp Ecology: Environment, Inc. 111 W Jackson Blvd Chicago, IL 60604 Fax 312-663-1090 Phone 312-663-9415									QA Level II 7 calendar day turnaround - vet 14 calendar day hardcopy
Relinquished by: (Signature) <i>Sally Innes</i>		Date / Time 5/27/94 / 1500		Received by: (Signature) <i>Timothy Calloway</i>		Ship To: PICKED UP: IEA LABS 126 West Centre Ctr. Schaumburg, IL 60195								
Relinquished by: (Signature)		Date / Time		Received by: (Signature)		ATTN: Jim Dawse 708-705-0740								
Relinquished by: (Signature) <i>Timothy Calloway</i>		Date / Time 5/31/94		Received for Laboratory by: (Signature) <i>[Signature]</i>		Date / Time 5/31/94 / 1:00		Airbill Number N/A						
Chain of Custody Seal Numbers														

Distribution: White - Accompanying Shipment; Pink - Coordinator Field Files; Yellow - Laboratory File

Activity Code:

ATTACHMENT D
COMMERCIAL LABORATORY ANALYTICAL RESULTS



ecology and environment, inc.

12251 UNIVERSAL, TAYLOR, MICHIGAN 48180, TEL. (313) 946-0900
International Specialists in the Environment

MEMORANDUM

DATE: June 23, 1994

TO: Sally Imes, Project Manager, E & E, Chicago, IL *SI*

FROM: Herbert B. Langer, TAT-Chemist, E & E, Detroit, MI *HL*

THRU: Sandra L. Basham, ATATL, E & E, Detroit, MI *SB*

SUBJ: Organic Data Quality Assurance Review, David Chemical,
Chicago, Cook County, IL

REF: Analytical TDD: T05-9405-807 Project TDD: T05-9405-010
Analytical PAN: EIL0638AAA Project PAN: EIL0638SAA

The data quality assurance review for the two waste samples collected from the David Chemical site in Chicago, Illinois, has been completed. Analyses for Semi-Volatile Organic Compounds (SW846, method 8270) was performed by National Environmental Testing Laboratories, Bartlett, Illinois.

The samples were numbered FS-01 and DOO2 corresponding to laboratory identification numbers 262670 and 262671, respectively.

Data Qualifications

I Holding Time: Acceptable

The samples were collected May 27, 1994, and analyzed May 31, and June 3, 1994, within the recommended holding times for the method and matrices.

II GC/MS Tuning: Acceptable

Decafluorotriphenylphosphene tuning compound was analyzed on each day of analysis. Ion abundance criteria were met for the instrument used.

III Initial and Continuing Calibration Verification: Acceptable

Initial calibration was performed May 22, 1994. All average response factors were greater than zero and percent relative

standard deviations between concentration response factors were less than thirty. Continuing calibration was performed each day of analysis. All relative response factors were greater than 0.05 and percent difference between average and relative response factors were less than twenty-five for detected compounds as required.

IV Method Blank: Acceptable

A method blank was analyzed at the beginning of each sample run. None of the target compounds were detected in the blanks above the instrument detection limit.

V Optional Quality Control Analyses:

A. Matrix Spike (MS) Analysis: Acceptable

A MS was prepared by the laboratory using the method blanks. Percent recoveries of the spike compounds were within the laboratory's quality control guidelines.

B. Surrogate Recovery: Acceptable

A total of six surrogates were added to each sample. Percent recoveries of the surrogate compounds were within the laboratory's quality control guidelines.

VI Compound Identification: Acceptable

Retention times for the identified compounds were within 0.06 units of the daily standards. All compounds present in the sample were present in the daily standards.

VII Compound Quantitation and Reported Detection Limits: Acceptable

Compound quantitation and reported detection limits correctly reflect dilution of the samples and the percent solids.

VIII Overall Assessment of Data for Use:

The overall usefulness of the data is based on the criteria outlined in OSWER Directive 9360.4-01 (April 1990), Data Validation Procedures, Section 4.0, BNAs by GC/MS Analysis.

Based upon the information provided, the data are acceptable for use.



ecology and environment. inc.

12251 UNIVERSAL, TAYLOR, MICHIGAN 48180. TEL. (313) 946-0900
International Specialists in the Environment

M E M O R A N D U M

DATE: June 23, 1994

TO: Sally Imes, Project Manager, E & E, Chicago, IL *SK*

FROM: Herbert B. Langer, TAT-Chemist, E & E, Detroit, MI *HL*

THRU: Sandra L. Basham, ATATL, E & E, Detroit, MI *SLB*

SUBJ: Organic Data Quality Assurance Review, David Chemical,
Chicago, Cook County, IL

REF: Analytical TDD: T05-9405-807 Project TDD: T05-9405-010
Analytical PAN: EIL0638AAA Project PAN: EIL0638SAA

The data quality assurance review for the waste sample collected from the David Chemical site in Chicago, Illinois, has been completed. Analysis for Volatile Organic Compounds (SW846, method 8240) and Alcohols (method 8015) was performed by National Environmental Testing Laboratories, Bartlett, Illinois, and Dallas, Texas.

The sample was numbered DO02 corresponding to laboratory identification number 262671.

Data Qualifications

I Holding Time: Acceptable

The sample was collected May 27, 1994. The sample was analyzed for volatiles June 4, 1994, and alcohols June 2, 1994, within the recommended holding times for the methods and matrices.

II GC/MS Tuning: Acceptable

Bromofluorobenzene tuning compound was analyzed on the day of volatile compound analysis. Ion abundance criteria were met for the instrument used. Alcohol analysis uses only GC instrumentation so GC/MS tuning was not required.

III Initial and Continuing Calibration Verification: Qualified

Initial GC/MS calibration was performed April 21, 1994. All average response factors were greater than zero and percent relative standard deviation between concentration response factors were less than thirty. Continuing calibration was performed on the day of analysis. All relative response factors were greater than 0.05 except acrolein. The non-detect result for this sample has been rejected. Percent difference between average and relative response factors were less than twenty-five as required.

Initial GC calibration was performed using all the target alcohols May 31, 1994. Continuing calibration was performed June 2, 1994. Peak response correlation for the standard concentrations was acceptable.

IV Method Blank: Acceptable

A method blank was analyzed with each analytical run. None of the target compounds were detected in the blank above the instrument detection limit.

V Optional Quality Control Analyses: Acceptable

A. Matrix Spike/Matrix Spike Duplicate (MS/MSD): Acceptable

Volatile MS and MSDs were prepared and analyzed along with the sample run. Percent recoveries and relative percent difference between MS and MSD results were within the laboratory's quality control guidelines.

B. Surrogate Recovery: No Action

Three surrogate compounds were added to the sample analyzed for volatile compounds. One surrogate compound recovery was outside the laboratory's quality control guidelines. Since this was an optional analysis no action was taken.

VI Compound Identification: Acceptable

All response times for the detected volatile and alcohol compounds were within 0.06 units of the daily standard except methanol. This is due to the response time range where methanol is detected and the result is considered acceptable as reported.

VII Compound Quantitation and Reported Detection Limits: Acceptable

Compound quantitation and the reported detection limits correctly reflect sample dilutions.

VIII Overall Assessment of Data for Use:

The overall usefulness of the data is based on the criteria outlined in OSWER Directive 9360.4-01 (April 1990), Data Validation Procedures, Section 5.0, VOAs by GC/MS Analysis.

Based upon the information provided, the data are acceptable for use with the above stated data qualifications.

Data Qualifiers and Definitions

- R - The sample results are rejected (analyte may or may not be present) due to gross deficiencies in quality control criteria. Resampling and/or reanalysis is necessary for verification.



ecology and environment. inc.

12251 UNIVERSAL TAYLOR, MICHIGAN 48180, TEL. (313) 946-0900

International Specialists in the Environment

MEMORANDUM

DATE: June 29, 1994

TO: Sally Imes, Project Manager, E & E, Chicago, IL *SI*

FROM: Herbert B. Langer, TAT-Chemist, E & E, Detroit, MI *HL*

THRU: Sandra L. Basham, ATATL, E & E, Detroit, MI *SLB*

SUBJ: **Flash Point and pH Data Quality Assurance Review, David Chemical, Chicago, Cook County, IL**

REF: Analytical TDD: T05-9405-807 Project TDD: T05-9405-010
Analytical PAN: EIL0638AAA Project PAN: EIL0638SAA

The data quality assurance review for the seven waste samples collected from the David Chemical site in Chicago, Illinois, has been completed. Analysis for pH (SW846, method 9045) and flash point (method 1010) was performed by IEA Laboratories, Schaumburg, Illinois.

The samples were numbered D001, D002, D003, BK-01, BG-01, PR-1, and FS-01, corresponding to laboratory identification 940964-001 through 940964-007.

Data Qualifications

I Holding Time: Acceptable

The samples were collected May 27, 1994. They were analyzed between May 31 and June 6, 1994. The sample was re-analyzed June 23, 1994, for flash point. The OSWER Directive 9360.4-01 does not include criteria regarding holding times for these methods.

II Calibration:

The lab used standard buffers with pH of 4.0, 7.0, and 10.0 to calibrate the instrument. A check sample was used to test the flash point equipment. The check sample flashed at the correct temperature.

III Flash Point

For a material to be considered ignitable under the Resource Conservation and Recovery Act (RCRA) the flash point must be determined using a "closed cup" analysis. The first sample analysis was performed using the "open cup" method. The sample was re-analyzed using the proper method.

VI Overall Assessment of Data for Use:

There are no criteria specified in the U.S. EPA OSWER Directive 9360.4-01 for the evaluation of pH and flash point analysis. Based on the calibration and review of the analytical method, the data is considered acceptable for use as reported.



ecology and environment. inc.

12251 UNIVERSAL TAYLOR MICHIGAN 48180. TEL. (313) 946-0900

International Specialists in the Environment

M E M O R A N D U M

DATE: June 23, 1994

TO: Sally Imes, Project Manager, E & E, Chicago, IL *SI*

FROM: Herbert B. Langer, TAT-Chemist, E & E, Detroit, MI *HL*

THRU: Sandra L. Basham, ATATL, E & E, Detroit, MI *SB*

SUBJ: **Inorganic Data Quality Assurance Review, David Chemical, Chicago, Cook County, IL**

REF: Analytical TDD: T05-9405-807 Project TDD: T05-9405-010
Analytical PAN: EIL0638AAA Project PAN: EIL0638SAA

The data quality assurance review for the seven waste samples collected from the David Chemical site in Chicago, Illinois has been completed. Analyses for total and Toxicity Characteristic Leaching Procedure metals (SW846, method 6010) listed in the Resource Conservation and Recovery Act, total and reactive cyanide and sulfide (methods 9030, 7.3.3.2, 9010, and 7.3.4.1), and mercury (method 7470) were performed by IEA Laboratories, Schaumburg, Illinois.

The samples were numbered D001, D002, D003, BK-01, BG-01, PR-1, and FS-01, corresponding to laboratory identification 940964-001 through 940964-007.

Data Qualifications

I Sample Holding Time: Acceptable

The samples were collected May 27, 1994. They were analyzed between June 2 and 8, 1994. All samples were analyzed within the correct holding times for the methods and matrices.

II Initial and Continuing Calibration Verification: Acceptable

Initial and continuing calibration standards were run for each analysis and analytical run. Recoveries of the target

compounds from the standards were within the recommended limits.

III Blanks: Acceptable

Blanks were analyzed with each analytical run. None of the target analytes were detected in the blanks above the instrument detection limits.

IV Interference Check Sample (ICS) Analysis: Acceptable

An ICS was run every eight hours. All ICS results were within the recommended control limits.

V Matrix Spike/Matrix Spike Duplicate (MS/MSD): Acceptable

MS and MSDs were prepared and analyzed with each sample run. Percent recoveries and percent differences between MS and MSD results were within the laboratory's quality control guidelines.

VI Overall Assessment of Data for Use

The overall usefulness of the data is based on the criteria outlined in OSWER Directive 9360.4-01 (April 1990), Data Validation Procedures, Section 3.0, Metallic Inorganic Parameters.

Based upon the information provided, the data are acceptable for use.



NATIONAL
ENVIRONMENTAL
TESTING, INC.

Bartlett Division
350 W. Bartlett Rd.
Bartlett, IL 60103
Tel: (708) 289-3100
Fax: (708) 289-5445

Ms. Mary Ripp
ECOLOGY & ENVIRONMENT, INC
111 West Jackson Blvd.
Chicago, IL 60604

06/09/1994

NET Job Number: 94.03926

Enclosed is the Quality Control Data and Analytical Results for the following samples submitted to NET, Inc. Bartlett Division for analysis:

Project Description: 2T 2054; T05-9405-807

Sample Number	Sample Description	Date Taken	Date Received
262670	FS-01; Grab	05/27/1994	05/31/1994
262671	D002; Grab	05/27/1994	05/31/1994

Sample analysis in support of the project referenced above has been completed and results are presented on the following pages. These results apply only to the samples analyzed. Reproduction of this report only in whole is permitted. Please refer to the enclosed "Key to Abbreviations" for definition of terms. Should you have questions regarding procedures or results, please do not hesitate to call. NET has been pleased to provide these analytical services for you.

This Quality Control report is generated on a batch basis. All information contained in this report is for the analytical batch(es) in which your sample(s) were analyzed.

Approved by:

Jean-Pierre C. Rouanet
Operations Manager





NATIONAL
ENVIRONMENTAL
TESTING, INC.

Bartlett Division
350 W. Bartlett Rd.
Bartlett, IL 60103
Tel. (708) 289-3100
Fax. (708) 289-5445

ANALYTICAL REPORT

Ms. Mary Ripp
ECOLOGY & ENVIRONMENT, INC
111 West Jackson Blvd.
Chicago, IL 60604

06/09/1994

Sample No. : 262670

NET Job No.: 94.03926

Sample Description: FS-01; Grab
2T 2054; T05-9405-807

Date Taken: 05/27/1994
Time Taken: 11:20
IEPA Cert. No. 100221

Date Received: 05/31/1994-
Time Received: 10:30
WDNR Cert. No. 999447130

Parameter	Results	Units	Date of Analysis	Method PQL	Analyst	Batch No. Prep/Run	Analytical Method
PREP, BN Nonaqueous	extracted		05/31/1994		las	180	3500 (1)
PREP, Acid Ext. Nonaqueous	extracted		05/31/1994		las	180	3500 (1)
ACID CMPS - 8270 NONAQUEOUS							
4-Chloro-3-methylphenol	<320	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
2-Chlorophenol	<320	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
2,4-Dichlorophenol	<320	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
2,4-Dimethylphenol	<320	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
2,4-Dinitrophenol	<1,600	ug/Kg	06/03/1994	1,650	rla	180 425	8270 (1)
2-Methyl-4,6-dinitrophenol	<1,600	ug/Kg	06/03/1994	1,650	rla	180 425	8270 (1)
2-Nitrophenol	<320	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
4-Nitrophenol	<1,600	ug/Kg	06/03/1994	1,650	rla	180 425	8270 (1)
Pentachlorophenol	<1,600	ug/Kg	06/03/1994	1,650	rla	180 425	8270 (1)
Phenol	<320	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
2,4,6-Trichlorophenol	<320	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
BASE/NEUTRALS-8270 NONAQUEOUS							
Acenaphthene	360	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
Acenaphthylene	<320	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
Anthracene	810	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
Benzidine	<1,600	ug/Kg	06/03/1994	1,650	rla	180 425	8270 (1)
Benzo(a)anthracene	2,000	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
Benzo(b)fluoranthene	1,900	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
Benzo(k)fluoranthene	1,400	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
Benzo(g,h,i)perylene	1,100	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
Benzo(a)pyrene	1,700	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
Benzyl butyl phthalate	400	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
Bis(2-chloroethoxy)methane	<320	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
Bis(2-chloroethyl)ether	<320	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
Bis(2-chloroisopropyl)ether	<320	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)





NATIONAL
ENVIRONMENTAL
TESTING, INC.

Bartlett Division
250 W. Bartlett Rd.
Bartlett, IL 60103
Tel (708) 289-3100
Fax: (708) 289-5445

ANALYTICAL REPORT

Ms. Mary Ripp
ECOLOGY & ENVIRONMENT, INC
111 West Jackson Blvd.
Chicago, IL 60604

06/09/1994

Sample No. : 262670

NET Job No.: 94.03926

Sample Description: FS-01; Grab
2T 2054; T05-9405-807

Date Taken: 05/27/1994
Time Taken: 11:20
IEPA Cert. No. 100221

Date Received: 05/31/1994
Time Received: 10:30
WDNR Cert. No. 999447130

Parameter	Results	Units	Date of Analysis	Method PQL	Analyst	Batch No. Prep/Run	Analytical Method
Bis(2-ethylhexyl)phthalate	3,040	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
4-Bromophenyl phenyl ether	<320	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
2-Chloronaphthalene	<320	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
4-Chlorophenyl phenyl ether	<320	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
Chrysene	2,200	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
Dibenzo(a,h)anthracene	530	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
Di-n-butyl phthalate	740	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
1,2-Dichlorobenzene	<320	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
1,3-Dichlorobenzene	<320	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
1,4-Dichlorobenzene	<320	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
3,3'-Dichlorobenzidine	<640	ug/Kg	06/03/1994	660	rla	180 425	8270 (1)
Diethyl phthalate	<320	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
Dimethyl phthalate	<320	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
2,4-Dinitrotoluene	<320	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
2,6-Dinitrotoluene	<320	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
Di-n-octyl phthalate	<320	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
Fluoranthene	4,900	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
Fluorene	420	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
Hexachlorobenzene	<320	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
Hexachlorobutadiene	<320	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
Hexachlorocyclopentadiene	<320	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
Hexachloroethane	<320	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
Indeno(1,2,3-cd)pyrene	1,100	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
Isophorone	<320	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
Naphthalene	<320	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
Nitrobenzene	<320	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
N-Nitrosodimethylamine	<320	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
N-Nitrosodi-n-propylamine	<320	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
N-Nitrosodiphenylamine	<320	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
Phenanthrene	2,270	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)





NATIONAL
ENVIRONMENTAL
TESTING, INC.

Bartlett Division
350 W. Bartlett Rd.
Bartlett, IL 60103
Tel (708) 289-3100
Fax (708) 289-5445

ANALYTICAL REPORT

Ms. Mary Ripp
ECOLOGY & ENVIRONMENT, INC
111 West Jackson Blvd.
Chicago, IL 60604

06/09/1994

Sample No. : 262670

NET Job No.: 94.03926

Sample Description: FS-01; Grab
2T 2054; T05-9405-807

Date Taken: 05/27/1994
Time Taken: 11:20
IEPA Cert. No. 100221

Date Received: 05/31/1994
Time Received: 10:30
WDNR Cert. No. 999447130

Parameter	Results	Units	Date of Analysis	Method PQL	Analyst	Batch No. Prep/Run	Analytical Method
Pyrene	3,600	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
1,2,4-Trichlorobenzene	<320	ug/Kg	06/03/1994	330	rla	180 425	8270 (1)
Surr: Phenol-d6	77	%	06/03/1994	10-94	rla	180 425	8270 (1)
Surr: 2-Fluorophenol	63	%	06/03/1994	21-100	rla	180 425	8270 (1)
Surr: Nitrobenzene-d5	81	%	06/03/1994	35-114	rla	180 425	8270 (1)
Surr: 2-Fluorobiphenyl	76	%	06/03/1994	43-116	rla	180 425	8270 (1)
Surr: Terphenyl-d14	89	%	06/03/1994	33-141	rla	180 425	8270 (1)
Surr: 2,4,6-Tribromophenol	117	%	06/03/1994	10-123	rla	180 425	8270 (1)





NATIONAL
ENVIRONMENTAL
TESTING, INC.

Bartlett Division
350 W. Bartlett Rd.
Bartlett, IL 60103
Tel: (708) 289-3100
Fax: (708) 289-5445

ANALYTICAL REPORT

Ms. Mary Ripp
ECOLOGY & ENVIRONMENT, INC
111 West Jackson Blvd.
Chicago, IL 60604

06/09/1994

Sample No. : 262671

NET Job No.: 94.03926

Sample Description: D002; Grab
2T 2054; T05-9405-807

Date Taken: 05/27/1994
Time Taken: 10:45
IEPA Cert. No. 100221

Date Received: 05/31/1994
Time Received: 10:30
WDNR Cert. No. 9994471307

Parameter	Results	Units	Date of Analysis	Method PQL	Analyst	Batch No. Prep/Run	Analytical Method
PREP, BM Nonaqueous	extracted		06/03/1994		las	181	3500 (1)
PREP, Acid Ext. Nonaqueous	extracted		06/03/1994		las	181	3500 (1)
ACID CMPS - 8270 NONAQUEOUS							
4-Chloro-3-methylphenol	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
2-Chlorophenol	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
2,4-Dichlorophenol	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
2,4-Dimethylphenol	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
2,4-Dinitrophenol	<500	mg/Kg	06/03/1994	1,650	rla	181 425	8270 (1)
2-Methyl-4,6-dinitrophenol	<500	mg/Kg	06/03/1994	1,650	rla	181 425	8270 (1)
2-Nitrophenol	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
4-Nitrophenol	<500	mg/Kg	06/03/1994	1,650	rla	181 425	8270 (1)
Pentachlorophenol	<500	mg/Kg	06/03/1994	1,650	rla	181 425	8270 (1)
Phenol	160	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
2,4,6-Trichlorophenol	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
BASE/NEUTRALS-8270 NONAQUEOUS							
Acenaphthene	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
Acenaphthylene	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
Anthracene	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
Benzidine	<500	mg/Kg	06/03/1994	1,650	rla	181 425	8270 (1)
Benzo(a)anthracene	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
Benzo(b)fluoranthene	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
Benzo(k)fluoranthene	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
Benzo(g,h,i)perylene	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
Benzo(a)pyrene	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
Benzyl butyl phthalate	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
Bis(2-chloroethoxy)methane	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
Bis(2-chloroethyl)ether	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
Bis(2-chloroisopropyl)ether	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)

See case narrative.





NATIONAL
ENVIRONMENTAL
TESTING, INC.

Bartlett Division
350 W Bartlett Rd.
Bartlett, IL 60103
Tel: (708) 289-3100
Fax: (708) 289-5445

ANALYTICAL REPORT

Ms. Mary Ripp
ECOLOGY & ENVIRONMENT, INC
111 West Jackson Blvd.
Chicago, IL 60604

06/09/1994

Sample No. : 262671

NET Job No.: 94.03926

Sample Description: D002; Grab
2T 2054; T05-9405-807

Date Taken: 05/27/1994
Time Taken: 10:45
IEPA Cert. No. 100221

Date Received: 05/31/1994
Time Received: 10:30
WDNR Cert. No. 999447130Z

Parameter	Results	Units	Date of Analysis	Method PQL	Analyst	Batch No. Prep/Run	Analytical Methods
Bis(2-ethylhexyl)phthalate	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
4-Bromophenyl phenyl ether	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
2-Chloronaphthalene	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
4-Chlorophenyl phenyl ether	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
Chrysene	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
Dibenzo(a,h)anthracene	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
Di-n-butyl phthalate	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
1,2-Dichlorobenzene	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
1,3-Dichlorobenzene	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
1,4-Dichlorobenzene	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
3,3'-Dichlorobenzidine	<200	mg/Kg	06/03/1994	660	rla	181 425	8270 (1)
Diethyl phthalate	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
Dimethyl phthalate	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
2,4-Dinitrotoluene	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
2,6-Dinitrotoluene	100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
Di-n-octyl phthalate	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
Fluoranthene	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
Fluorene	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
Hexachlorobenzene	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
Hexachlorobutadiene	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
Hexachlorocyclopentadiene	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
Hexachloroethane	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
Indeno(1,2,3-cd)pyrene	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
Isophorone	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
Naphthalene	120	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
Nitrobenzene	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
N-Nitrosodimethylamine	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
N-Nitrosodi-n-propylamine	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
N-Nitrosodiphenylamine	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
Phenanthrene	380	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)

See case narrative.





NATIONAL
ENVIRONMENTAL
TESTING, INC.

Bartlett Division
350 W. Bartlett Rd.
Bartlett, IL 60103
Tel: (708) 289-3100
Fax: (708) 289-5445

ANALYTICAL REPORT

Ms. Mary Ripp
ECOLOGY & ENVIRONMENT, INC
111 West Jackson Blvd.
Chicago, IL 60604

06/09/1994

Sample No. : 262671

NET Job No.: 94.03926

Sample Description: D002; Grab
2T 2054; T05-9405-807

Date Taken: 05/27/1994
Time Taken: 10:45
IEPA Cert. No. 100221

Date Received: 05/31/1994
Time Received: 10:30
WDNR Cert. No. 9994471307

Parameter	Results	Units	Date of Analysis	Method PQL	Analyst	Batch No. Prep/Run	Analytical Method
Pyrene	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
1,2,4-Trichlorobenzene	<100	mg/Kg	06/03/1994	330	rla	181 425	8270 (1)
Surr: Phenol-d6	D	%	06/03/1994	10-94	rla	181 425	8270 (1)
Surr: 2-Fluorophenol	D	%	06/03/1994	21-100	rla	181 425	8270 (1)
Surr: Nitrobenzene-d5	D	%	06/03/1994	35-114	rla	181 425	8270 (1)
Surr: 2-Fluorobiphenyl	D	%	06/03/1994	43-116	rla	181 425	8270 (1)
Surr: Terphenyl-d14	D	%	06/03/1994	33-141	rla	181 425	8270 (1)
Surr: 2,4,6-Tribromophenol	D	%	06/03/1994	10-123	rla	181 425	8270 (1)
VOLATILES - 8240 NONAQUEOUS							
Acrolein	<100,000	ug/Kg	06/04/1994	100	adl	412	8240 (1)
Acrylonitrile	<100,000	ug/Kg	06/04/1994	100	adl	412	8240 (1)
Benzene	<5,000	ug/Kg	06/04/1994	5.0	adl	412	8240 (1)
Bromodichloromethane	<5,000	ug/Kg	06/04/1994	5.0	adl	412	8240 (1)
Bromoform	<5,000	ug/Kg	06/04/1994	5.0	adl	412	8240 (1)
Bromomethane	<10,000	ug/Kg	06/04/1994	10	adl	412	8240 (1)
Carbon tetrachloride	<5,000	ug/Kg	06/04/1994	5.0	adl	412	8240 (1)
Chlorobenzene	<5,000	ug/Kg	06/04/1994	5.0	adl	412	8240 (1)
Chloroethane	<10,000	ug/Kg	06/04/1994	10	adl	412	8240 (1)
2-Chloroethylvinyl ether	<10,000	ug/Kg	06/04/1994	10	adl	412	8240 (1)
Chloroform	<5,000	ug/Kg	06/04/1994	5.0	adl	412	8240 (1)
Chloromethane	<10,000	ug/Kg	06/04/1994	10	adl	412	8240 (1)
Dibromochloromethane	<5,000	ug/Kg	06/04/1994	5.0	adl	412	8240 (1)
1,2-Dichlorobenzene	<5,000	ug/Kg	06/04/1994	5.0	adl	412	8240 (1)
1,3-Dichlorobenzene	<5,000	ug/Kg	06/04/1994	5.0	adl	412	8240 (1)
1,4-Dichlorobenzene	<5,000	ug/Kg	06/04/1994	5.0	adl	412	8240 (1)
1,1-Dichloroethane	5,500	ug/Kg	06/04/1994	5.0	adl	412	8240 (1)
1,2-Dichloroethane	<5,000	ug/Kg	06/04/1994	5.0	adl	412	8240 (1)
1,1-Dichloroethene	<5,000	ug/Kg	06/04/1994	5.0	adl	412	8240 (1)
trans-1,2-Dichloroethene	<5,000	ug/Kg	06/04/1994	5.0	adl	412	8240 (1)

See case narrative.





NATIONAL
ENVIRONMENTAL
TESTING, INC.

Bartlett Division
350 W. Bartlett Rd.
Bartlett, IL 60103
Tel: (708) 289-3100
Fax: (708) 289-5445

ANALYTICAL REPORT

Ms. Mary Ripp
ECOLOGY & ENVIRONMENT, INC
111 West Jackson Blvd.
Chicago, IL 60604

06/09/1994

Sample No. : 262671

NET Job No.: 94.03926

Sample Description: D002; Grab
2T 2054; T05-9405-807

Date Taken: 05/27/1994
Time Taken: 10:45
IEPA Cert. No. 100221

Date Received: 05/31/1994
Time Received: 10:30
WDNR Cert. No. 999447130

Parameter	Results	Units	Date of Analysis	Method PQL	Analyst	Batch No. Prep/Run	Analytical Method
cis-1,2-Dichloroethene	<5,000	ug/Kg	06/04/1994	5.0	adl	412 8240 (1)	
1,2-Dichloropropane	<5,000	ug/Kg	06/04/1994	5.0	adl	412 8240 (1)	
cis-1,3-Dichloropropene	<5,000	ug/Kg	06/04/1994	5.0	adl	412 8240 (1)	
trans-1,3-Dichloropropene	<5,000	ug/Kg	06/04/1994	5.0	adl	412 8240 (1)	
Ethyl benzene	21,000	ug/Kg	06/04/1994	5.0	adl	412 8240 (1)	
Methylene chloride	12,200,000 *	ug/Kg	06/04/1994	5.0	adl	412 8240 (1)	
1,1,2,2-Tetrachloroethane	<5,000	ug/Kg	06/04/1994	5.0	adl	412 8240 (1)	
Tetrachloroethene	<5,000	ug/Kg	06/04/1994	5.0	adl	412 8240 (1)	
Toluene	165,000	ug/Kg	06/04/1994	5.0	adl	412 8240 (1)	
1,1,1-Trichloroethane	265,000	ug/Kg	06/04/1994	5.0	adl	412 8240 (1)	
1,1,2-Trichloroethane	<5,000	ug/Kg	06/04/1994	5.0	adl	412 8240 (1)	
Trichloroethene	9,500	ug/Kg	06/04/1994	5.0	adl	412 8240 (1)	
Trichlorofluoromethane	<5,000	ug/Kg	06/04/1994	5.0	adl	412 8240 (1)	
Vinyl chloride	<10,000	ug/Kg	06/04/1994	10	adl	412 8240 (1)	
Xylenes, Total	138,000	ug/Kg	06/04/1994	5.0	adl	412 8240 (1)	
Surr: 1,2-Dichloroethane-d4	95	%	06/04/1994	70-121	adl	412 8240 (1)	
Surr: Toluene-d8	100	%	06/04/1994	81-117	adl	412 8240 (1)	
Surr: Bromofluorobenzene	168	%	06/04/1994	74-121	adl	412 8240 (1)	
F001-5 ALCOHOL COMPOUNDS							
Butanol	<120	ug/g	06/02/1994	20	tms	21 8015 (1)	
2-Ethoxyethanol	15,600	ug/g	06/02/1994	20	tms	21 8015 (1)	
Isobutanol	<590	ug/g	06/02/1994	20	tms	21 8015 (1)	
Methanol	1,200	ug/g	06/02/1994	20	tms	21 8015 (1)	

See case narrative.

* Parameter analysis performed at a 20,000x dilution





NATIONAL
ENVIRONMENTAL
TESTING, INC.

Bartlett Division
350 W. Bartlett Rd.
Bartlett, IL 60103
Tel: (708) 289-3100
Fax: (708) 289-5445

CASE NARRATIVE

Ms. Mary Ripp
ECOLOGY & ENVIRONMENT, INC
111 West Jackson Blvd.
Chicago, IL 60604

06/09/1994

NET Job Number: 94.03926

Project Description: 2T 2054; T05-9405-807

Sample Number	Sample Description	Date Taken	Date Received
262670	FS-01; Grab	05/27/1994	05/31/1994
262671	D002; Grab	05/27/1994	05/31/1994

Sample analysis in support of the project referenced above has been completed and results are presented on the following pages. Please refer to the enclosed "Key to Abbreviations" for definition of terms.

Due to the oily matrix of sample 262671, the following comments should be noted for the indicated fractions;

Volatile Organic Analysis

A medium level extraction of the sample was necessary for analysis. As a result, the results are reported at a 5000x dilution. The result obtained for methylene chloride at this dilution was above calibration range, and a further dilution of 20,000x was required.

The recovery of Bromofluorobenzene was above control limits. This was due to matrix interference.

Semi-Volatile Organic Analysis

The sample was prepared for analysis by diluting 1.0 g to a final volume of 10 mls. As a result, the results are reported at a 300x dilution. Any surrogate present was diluted out.





NATIONAL
ENVIRONMENTAL
TESTING, INC.

Bartlett Division
250 W. Bartlett Rd.
Bartlett, IL 60103
Tel: (708) 289-3100
Fax: (708) 289-5445

Alcohol Analysis

The reporting limits are elevated due to matrix interference.

Due to the nonaqueous nature of the sample, the results reported have been density corrected.

This Quality Control report is generated on a batch basis. All information contained in this report is for the analytical batch(es) in which your samples were analyzed. These results apply only to the samples analyzed. Reproduction of this report only in whole is permitted. Please refer to the enclosed "Key to Abbreviations" for definition of terms. Should you have questions regarding procedures or results, please do not hesitate to call. NET has been pleased to provide these analytical services for you.

Approved By:

Ray Kalicki
Quality Assurance Coordinator





NATIONAL
ENVIRONMENTAL
TESTING, INC.

Bartlett Division
350 W. Bartlett Rd.
Bartlett, IL 60103
Tel: (708) 289-3100
Fax: (708) 289-5445

QUALITY CONTROL REPORT

CONTINUING CALIBRATION VERIFICATION

ECOLOGY & ENVIRONMENT, INC
111 West Jackson Blvd.
Chicago, IL 60604

06/09/1994

NET Job Number: 94.03926

Ms. Mary Ripp

Analyte	Run	CCV	Conc.	Percent Recovery
	Batch Number	True Conc.		
ACID CMPDS - 8270 NONAQUEOUS				
Surr: 2-Fluorophenol	425	50.0	50.0	100.0
Surr: Phenol-d6	425	100	108	108.0
BASE/NEUTRALS-8270 NONAQUEOUS				
Acenaphthene	425	50.0	51.0	102.0
Benzo(a)pyrene	425	50.0	53.4	106.8
1,4-Dichlorobenzene	425	50.0	52.5	105.0
Di-n-octyl phthalate	425	50.0	57.7	115.4
Surr: 2-Fluorobiphenyl	425	50.0	50.7	101.4
Fluoranthene	425	50.0	50.6	101.2
Hexachlorobutadiene	425	50.0	52.0	104.0
Surr: Nitrobenzene-d5	425	50.0	54.1	108.2
N-Nitrosodiphenylamine	425	50.0	54.1	108.2
VOLATILES - 8240 NONAQUEOUS				
Chloroform	412	50.0	52.2	104.4
1,1-Dichloroethane	412	50.0	54.5	109.0
1,2-Dichloropropane	412	50.0	50.7	101.4
Ethyl benzene	412	50.0	57.1	114.2
Toluene	412	50.0	53.4	106.8
Vinyl chloride	412	50.0	53.1	106.2

CCV - Continuing Calibration Verification





NATIONAL
ENVIRONMENTAL
TESTING, INC.

Bartlett Division
350 W. Bartlett Rd.
Bartlett, IL 60103
Tel: (708) 289-3100
Fax: (708) 289-5445

QUALITY CONTROL REPORT

CONTINUING CALIBRATION VERIFICATION

ECOLOGY & ENVIRONMENT, INC
111 West Jackson Blvd.
Chicago, IL 60604

06/09/1994

NET Job Number: 94.03926

Ms. Mary Ripp

Analyte	Run Batch Number	CCV True Conc.	Conc. Found	Percent Recovery
F001-5 ALCOHOL COMPOUNDS				
Butanol	21	20.0	21.5	107.5
2-Ethoxyethanol	21	20.3	21.3	104.9
Isobutanol	21	19.9	21.5	108.0
Methanol	21	20.0	22.2	111.0

CCV - Continuing Calibration Verification





NATIONAL
ENVIRONMENTAL
TESTING, INC.

Bartlett Division
350 W. Bartlett Rd.
Bartlett, IL 60103
Tel: (708) 289-3100
Fax: (708) 289-5445

QUALITY CONTROL REPORT

BLANK ANALYSIS

ECOLOGY & ENVIRONMENT, INC
111 West Jackson Blvd.
Chicago, IL 60604

06/09/1994

NET Job Number: 94.03926

Ms. Mary Ripp

Analyte	Prep Batch Number	Run Batch Number	Blank Analysis Results	Units	Reporting Limit	Analytical Method
ACID CMPS - 8270 NOMAQUEOUS						8270 (1)
4-Chloro-3-methylphenol	180	414	<330	ug/Kg	330	8270 (1)
2-Chlorophenol	180	414	<330	ug/Kg	330	8270 (1)
2,4-Dichlorophenol	180	414	<330	ug/Kg	330	8270 (1)
2,4-Dimethylphenol	180	414	<330	ug/Kg	330	8270 (1)
2,4-Dinitrophenol	180	414	<1600	ug/Kg	1,650	8270 (1)
2-Methyl-4,6-dinitrophenol	180	414	<1600	ug/Kg	1,650	8270 (1)
2-Nitrophenol	180	414	<330	ug/Kg	330	8270 (1)
4-Nitrophenol	180	414	<1600	ug/Kg	1,650	8270 (1)
Pentachlorophenol	180	414	<1600	ug/Kg	1,650	8270 (1)
Phenol	180	414	<330	ug/Kg	330	8270 (1)
2,4,6-Trichlorophenol	180	414	<330	ug/Kg	330	8270 (1)
Surr: Phenol-d6	180	414	56	%	10-94	8270 (1)
Surr: 2-Fluorophenol	180	414	52	%	21-100	8270 (1)
Surr: 2,4,6-Tribromophenol	180	414	81	%	10-123	8270 (1)
BASE/NEUTRALS-8270 NOMAQUEOUS						8270 (1)
Acenaphthene	180	414	<330	ug/Kg	330	8270 (1)
Acenaphthylene	180	414	<330	ug/Kg	330	8270 (1)
Anthracene	180	414	<330	ug/Kg	330	8270 (1)
Benzidine	180	414	<1600	ug/Kg	1,650	8270 (1)
Benzo(a)anthracene	180	414	<330	ug/Kg	330	8270 (1)
Benzo(b)fluoranthene	180	414	<330	ug/Kg	330	8270 (1)
Benzo(k)fluoranthene	180	414	<330	ug/Kg	330	8270 (1)
Benzo(g,h,i)perylene	180	414	<330	ug/Kg	330	8270 (1)
Benzo(a)pyrene	180	414	<330	ug/Kg	330	8270 (1)
Benzyl butyl phthalate	180	414	<330	ug/Kg	330	8270 (1)
Bis(2-chloroethoxy)methane	180	414	<330	ug/Kg	330	8270 (1)

Advisory Control Limits for Blanks:

All compounds should be less than the Reporting Limit, except for phthalate esters, toluene, methylene chloride, acetone and chloroform should be less than 5 times the Reporting Limit.





NATIONAL
ENVIRONMENTAL
TESTING, INC.

Bartlett Division
350 W. Bartlett Rd.
Bartlett, IL 60103
Tel: (708) 289-3100
Fax: (708) 289-5445

QUALITY CONTROL REPORT

BLANK ANALYSIS

ECOLOGY & ENVIRONMENT, INC
111 West Jackson Blvd.
Chicago, IL 60604

06/09/1994

NET Job Number: 94.03926

Ms. Mary Ripp

Analyte	Prep Batch Number	Run Batch Number	Blank Analysis Results	Units	Reporting Limit	Analytical Method
Bis(2-chloroethyl)ether	180	414	<330	ug/Kg	330	8270 (1)
Bis(2-chloroisopropyl)ether	180	414	<330	ug/Kg	330	8270 (1)
Bis(2-ethylhexyl)phthalate	180	414	<330	ug/Kg	330	8270 (1)
4-Bromophenyl phenyl ether	180	414	<330	ug/Kg	330	8270 (1)
2-Chloronaphthalene	180	414	<330	ug/Kg	330	8270 (1)
4-Chlorophenyl phenyl ether	180	414	<330	ug/Kg	330	8270 (1)
Chrysene	180	414	<330	ug/Kg	330	8270 (1)
Dibenzo(a,h)anthracene	180	414	<330	ug/Kg	330	8270 (1)
Di-n-butyl phthalate	180	414	<330	ug/Kg	330	8270 (1)
1,2-Dichlorobenzene	180	414	<330	ug/Kg	330	8270 (1)
1,3-Dichlorobenzene	180	414	<330	ug/Kg	330	8270 (1)
1,4-Dichlorobenzene	180	414	<330	ug/Kg	330	8270 (1)
3,3'-Dichlorobenzidine	180	414	<660	ug/Kg	660	8270 (1)
Diethyl phthalate	180	414	<330	ug/Kg	330	8270 (1)
Dimethyl phthalate	180	414	<330	ug/Kg	330	8270 (1)
2,4-Dinitrotoluene	180	414	<330	ug/Kg	330	8270 (1)
2,6-Dinitrotoluene	180	414	<330	ug/Kg	330	8270 (1)
Di-n-octyl phthalate	180	414	<330	ug/Kg	330	8270 (1)
Fluoranthene	180	414	<330	ug/Kg	330	8270 (1)
Fluorene	180	414	<330	ug/Kg	330	8270 (1)
Hexachlorobenzene	180	414	<330	ug/Kg	330	8270 (1)
Hexachlorobutadiene	180	414	<330	ug/Kg	330	8270 (1)
Hexachlorocyclopentadiene	180	414	<330	ug/Kg	330	8270 (1)
Hexachloroethane	180	414	<330	ug/Kg	330	8270 (1)
Indeno(1,2,3-cd)pyrene	180	414	<330	ug/Kg	330	8270 (1)
Isophorone	180	414	<330	ug/Kg	330	8270 (1)
Naphthalene	180	414	<330	ug/Kg	330	8270 (1)
Nitrobenzene	180	414	<330	ug/Kg	330	8270 (1)
N-Nitrosodimethylamine	180	414	<330	ug/Kg	330	8270 (1)

Advisory Control Limits for Blanks:

All compounds should be less than the Reporting Limit, except for phthalate esters, toluene, methylene chloride, acetone and chloroform should be less than 5 times the Reporting Limit.





NATIONAL
ENVIRONMENTAL
TESTING, INC.

Bartlett Division
350 W. Bartlett Rd.
Bartlett, IL 60103
Tel: (708) 289-3100
Fax: (708) 289-5445

QUALITY CONTROL REPORT

BLANK ANALYSIS

ECOLOGY & ENVIRONMENT, INC
111 West Jackson Blvd.
Chicago, IL 60604

06/09/1994

NET Job Number: 94.03926

Ms. Mary Ripp

Analyte	Prep Batch Number	Run Batch Number	Blank Analysis Results	Units	Reporting Limit	Analytical Method
N-Nitrosodi-n-propylamine	180	414	<330	ug/Kg	330	8270 (1)
N-Nitrosodiphenylamine	180	414	<330	ug/Kg	330	8270 (1)
Phenanthrene	180	414	<330	ug/Kg	330	8270 (1)
Pyrene	180	414	<330	ug/Kg	330	8270 (1)
1,2,4-Trichlorobenzene	180	414	<330	ug/Kg	330	8270 (1)
Surr: Nitrobenzene-d5	180	414	57	%	35-114	8270 (1)
Surr: 2-Fluorobiphenyl	180	414	59	%	43-116	8270 (1)
Surr: Terphenyl-d14	180	414	84	%	33-141	8270 (1)
VOLATILES - 8240 NONAQUEOUS						8240 (1)
Acrolein		412	<100	ug/Kg	100	8240 (1)
Acrylonitrile		412	<100	ug/Kg	100	8240 (1)
Benzene		412	<5.0	ug/Kg	5.0	8240 (1)
Bromodichloromethane		412	<5.0	ug/Kg	5.0	8240 (1)
Bromoform		412	<5.0	ug/Kg	5.0	8240 (1)
Carbon tetrachloride		412	<5.0	ug/Kg	5.0	8240 (1)
Chlorobenzene		412	<5.0	ug/Kg	5.0	8240 (1)
2-Chloroethylvinyl ether		412	<10.0	ug/Kg	10.0	8240 (1)
Chloroethane		412	<10.0	ug/Kg	10.0	8240 (1)
Chloroform		412	<5.0	ug/Kg	5.0	8240 (1)
Dibromochloromethane		412	<5.0	ug/Kg	5.0	8240 (1)
1,4-Dichlorobenzene		412	<5.0	ug/Kg	5.0	8240 (1)
1,1-Dichloroethane		412	<5.0	ug/Kg	5.0	8240 (1)
1,2-Dichloroethane		412	<5.0	ug/Kg	5.0	8240 (1)
1,1-Dichloroethane		412	<5.0	ug/Kg	5.0	8240 (1)
trans-1,2-Dichloroethane		412	<5.0	ug/Kg	5.0	8240 (1)
1,2-Dichloropropene		412	<5.0	ug/Kg	5.0	8240 (1)
cis-1,3-Dichloropropene		412	<5.0	ug/Kg	5.0	8240 (1)
trans-1,3-Dichloropropene		412	<5.0	ug/Kg	5.0	8240 (1)

Advisory Control Limits for Blanks:

All compounds should be less than the Reporting Limit, except for phthalate esters, toluene, methylene chloride, acetone and chloroform should be less than 5 times the Reporting Limit.





NATIONAL
ENVIRONMENTAL
TESTING, INC.

Bartlett Division
350 W. Bartlett Rd.
Bartlett, IL 60103
Tel: (708) 289-3100
Fax: (708) 289-5445

QUALITY CONTROL REPORT

BLANK ANALYSIS

ECOLOGY & ENVIRONMENT, INC
111 West Jackson Blvd.
Chicago, IL 60604

06/09/1994

NET Job Number: 94.03926

Ms. Mary Ripp

Analyte	Prep Batch Number	Run Batch Number	Blank Analysis Results	Units	Reporting Limit	Analytical Method
Ethyl benzene		412	<5.0	ug/Kg	5.0	8240 (1)
Methylene chloride		412	<5.0	ug/Kg	5.0	8240 (1)
Tetrachloroethene		412	<5.0	ug/Kg	5.0	8240 (1)
Toluene		412	<5.0	ug/Kg	5.0	8240 (1)
1,1,1-Trichloroethane		412	<5.0	ug/Kg	5.0	8240 (1)
1,1,2-Trichloroethane		412	<5.0	ug/Kg	5.0	8240 (1)
Trichloroethene		412	<5.0	ug/Kg	5.0	8240 (1)
Trichlorofluoromethane		412	<5.0	ug/Kg	5.0	8240 (1)
Vinyl chloride		412	<10.0	ug/Kg	10.0	8240 (1)
Xylenes, Total		412	<5.0	ug/Kg	5.0	8240 (1)
Surr: 1,2-Dichloroethane-d4		412	100	%	70-121	8240 (1)
Surr: Toluene-d8		412	101	%	81-117	8240 (1)
Surr: Bromofluorobenzene		412	99	%	74-121	8240 (1)
F001-5 ALCOHOL COMPOUNDS						8015 (1)
Butanol		21	<1.0	mg/L	20	8015 (1)
2-Ethoxyethanol		21	<10	mg/L	20	8015 (1)
Isobutanol		21	<1.0	mg/L	20	8015 (1)
Methanol		21	<1.0	mg/L	20	8015 (1)

Advisory Control Limits for Blanks:

All compounds should be less than the Reporting Limit, except for phthalate esters, toluene, methylene chloride, acetone and chloroform should be less than 5 times the Reporting Limit.





NATIONAL
ENVIRONMENTAL
TESTING, INC.

Bartlett Division
550 W. Bartlett Rd.
Bartlett, IL 60103
Tel: (708) 289-3100
Fax: (708) 289-5445

QUALITY CONTROL REPORT

LABORATORY CONTROL STANDARD

ECOLOGY & ENVIRONMENT, INC
111 West Jackson Blvd.
Chicago, IL 60604

06/09/1994

NET Job Number: 94.03926

Ms. Mary Ripp

Analyte	Prep Batch Number	Run Batch Number	True Conc.	Conc. Found	LCS % Recovery
VOLATILES - 8240 NONAQUEOUS					
Benzene		412	20.0	22.0	110.0
Chlorobenzene		412	20.0	22.0	110.0
Chloroform		412	20.0	22.0	110.0
1,1-Dichloroethene		412	20.0	24.0	120.0
1,2-Dichloropropane		412	20.0	22.0	110.0
Toluene		412	20.0	22.0	110.0
Trichloroethene		412	20.0	21.0	105.0

Advisory Control Limits - Inorganics - LCS recovery should be 80 - 120%.



NET Midwest, Bartlett Division

KEY TO ABBREVIATIONS and METHOD REFERENCES

<	: Less than; When appearing in the results column indicates the analyte was not detected at or above the reported value.
mg/L	: Concentration in units of milligrams of analyte per liter of sample. Measurement used for aqueous samples. Can also be expressed as parts per million (ppm).
ug/g	: Concentration in units of micrograms of analyte per gram of sample. Measurement used for non-aqueous samples. Can also be expressed as parts per million (ppm) or mg/Kg.
ug/L	: Concentration in units of micrograms of analyte per liter of sample. Measurement used for aqueous samples. Can also be expressed as parts per billion (ppb).
ug/Kg	: Concentration in units of micrograms of analyte per kilogram of sample. Measurement used for non-aqueous samples. Can also be expressed as parts per billion (ppb).
B	: Sample result flag indicating that the analyte was also found in the method blank analysis. The value after the B indicates the concentration found in the blank analysis.
D	: Sample result flag indicating that the reported concentration is from an analysis performed at a dilution. The value following the D indicates the dilution factor of the analysis.
J	: Sample result flag indicating that the reported concentration is below the routine reporting limit but greater than the Method Detection Limit. The value should be considered estimated.
TCLP	: These initials appearing in front of an analyte name indicate that the Toxicity Characteristic Leaching Procedure (TCLP) was performed for this test.
%	: Percent; To convert ppm to %, divide the result by 10,000. To convert % to ppm, multiply the result by 10,000.
Dry Weight (dw)	: When indicated, the results are reported on a dry weight basis. The contribution of the moisture content in the sample is subtracted when calculating the concentration of the analyte.
ICP	: Indicates analysis was performed using Inductively Coupled Plasma Spectroscopy.
AA	: Indicates analysis was performed using Atomic Absorption Spectroscopy.
GFAA	: Indicates analysis was performed using Graphite Furnace Atomic Absorption Spectroscopy.
PQL	: Practical Quantitation Limit; the lowest level that can be reliably achieved within specified limits of precision and accuracy during routine laboratory operating conditions.

Method References

- (1) Methods 1000 through 9999: see "Test Methods for Evaluating Solid Waste", USEPA SW-846, 3rd Edition, 1986.
- (2) ASTM "American Society for Testing Materials"
- (3) Methods 100 through 499: see "Methods for Chemical Analysis of Water and Wastes", USEPA, 600/4-79-020, Rev. 1983.
- (4) See "Standard Methods for the Examination of Water and Wastewater", 17th Ed, APHA, 1989.
- (5) Methods 600 through 625: see "Guidelines Establishing Test Procedures for the Analysis of Pollutants", USEPA Federal Register Vol. 49 No. 209, October 1984.
- (6) Methods 500 through 599: see "Methods for the Determination of Organic Compounds in Drinking Water," USEPA 600/4-88/039, Rev. 1988.



IEA
An Aquarion Company

Client: E & E
IEA Job#: CH940964
Project #: T05-9405-807

ANALYTE LIST
mg/L

Matrix: LIQUID

Client ID	D001	D003	PR-1			Date	PQL
Lab ID	940964	940964	940964			Analyzed	
	001	003	004				
Analyte	Method						
Arsenic	6010	0.57	12**	<0.5**		06/03/94	0.1
Barium	6010	0.42	<0.50	<0.5		06/03/94	0.05
Cadmium	6010	0.0052	<0.25	<0.05		06/03/94	0.005
Chromium	6010	0.33	120000	24000		06/03/94	0.01
Lead	6010	0.50	<2.5	<0.50		06/03/94	0.05
Mercury	7470	0.0072	<0.002	<0.002		06/06/94	0.002
Selenium	6010	<0.1	<6.0*	<6.0*		06/03/94	0.1
Silver	6010	<0.01	<0.50	0.14		06/03/94	0.01

PQL = Practical Quantitation Limit

**Analysis method 7060 on 6/9/94 PQL#3 1mg/l PQL #4 0.5mg/l
* Analysis method 7740 on 6/9/94 PQL 6.0 mg/l



IEA
An Aquarion Company

CLIENT: E & E
CLIENT ID: BG-01
LAB ID: 940964006

TCLP ANALYTICAL RESULTS

EPA WASTE #	CONTAMINANT/ DATE LEACH:06/01/94 DATE EXTRACT:06/02/94	METHOD	DATE ANALY	REG LIMIT (mg/L)	DETECTION LIMIT (mg/L)	AMOUNT DETECTED (mg/L)
	METALS					
D004	Arsenic	6010	06/03/94	5.0	0.1	<0.1
D005	Barium	6010	06/03/94	100.0	0.05	0.43
D006	Cadmium	6010	06/08/94	1.0	0.005	<0.005
D007	Chromium	6010	06/08/94	5.0	0.01	<0.01
D008	Lead	6010	06/03/94	5.0	0.05	<0.05
D009	Mercury	7470	06/06/94	0.2	0.0002	<0.0002
D010	Selenium	6010	06/03/94	1.0	0.1	<0.1
D011	Silver	6010	06/08/94	5.0	0.01	<0.01



IEA
An Aquarion Company

CLIENT: E & E
CLIENT ID: BK-01
LAB ID: 940964005

TCLP ANALYTICAL RESULTS

EPA WASTE #	CONTAMINANT/ DATE LEACH:06/01/94 DATE EXTRACT:06/02/94		DATE ANALY	REG LIMIT (mg/L)	DETECTION LIMIT (mg/L)	AMOUNT DETECTED (mg/L)
	METALS	METHOD				
D004	Arsenic	6010	06/03/94	5.0	0.1	0.78
D005	Barium	6010	06/03/94	100.0	0.05	0.54
D006	Cadmium	6010	06/08/94	1.0	0.005	0.0073
D007	Chromium	6010	06/03/94	5.0	0.01	630
D008	Lead	6010	06/03/94	5.0	0.05	0.084
D009	Mercury	7470	06/06/94	0.2	0.0002	<0.0002
D010	Selenium	6010	06/08/94	1.0	0.1	<0.1
D011	Silver	6010	06/08/94	5.0	0.01	<0.01



IEA
An Aquarion Company

CLIENT: E & E
CLIENT ID: FS-01
LAB ID: 940964007

TCLP ANALYTICAL RESULTS

EPA WASTE #	CONTAMINANT/ DATE LEACH: 06/01/94 DATE EXTRACT: 06/02/94	METHOD	DATE ANALY	REG LIMIT (mg/L)	DETECTION LIMIT (mg/L)	AMOUNT DETECTED (mg/L)
	METALS		06/03/94			
D004	Arsenic	6010	06/03/94	5.0	0.1	<0.1
D005	Barium	6010	06/03/94	100.0	0.05	0.59
D006	Cadmium	6010	06/08/94	1.0	0.005	0.033
D007	Chromium	6010	06/08/94	5.0	0.01	11.0
D008	Lead	7470	06/03/94	5.0	0.05	<0.05
D009	Mercury	6010	06/06/94	0.2	0.0002	<0.0002
D010	Selenium	6010	06/03/94	1.0	0.1	<0.1
D011	Silver	6010	06/03/94	5.0	0.01	<0.01



Project #: T05-9405-807

Matrix: LIQUID

[illegible]

PQL = Practical Quantitation Limit



IEA
An Aquanor Company

Client: E & E
IEA Job #: CH940964
Project #: T05-9405-807

ANALYTE LIST

Matrix: LIQUID

		Client ID				Date Analyzed	PQL
		D001	D003	PR-1	D002		
		940964	940964	940964	940964		
Lab ID		001	003	004	002		
Analyte	Method						
P.H.	150.1	<1.0	<1.0	3.5		05/31/94	
O.C. Flashpoint	1010				>200	06/06/94	F
Total Sulfide	9030		<10.0			06/02/94	10 mg/kg
Reactive Sulfide	7.3 4.1		<10.0			06/03/94	10 mg/kg
Total Cyanide	9010		<0.5			06/03/94	0.5 mg/kg
Reactive Cyanide	7.3 3.2		<1.0			06/03/94	1 mg/kg

PQL = Practical Quantitation Limit



IEA
An Aquarion Company

CASE NARRATIVE

Job #CH940964

The 2nd flashpoint performed on 6-23-94 was a closed cup flashpoint. The previous analysis on 6-6-94 was an open cup flashpoint. The closed cup flashpoint captures more of the volatile vapors and, therefore, flashes at a lower temperature than an open cup flashpoint. Open cup flashpoint, on the other hand, is opened to the surrounding air and has less concentrated vapors as compared to a closed cup flashpoint.



Client: E & E
IEA Job #: CH940964
Project #: T05-9405-807

ANALYTE LIST

Matrix: Liquid

[illegible]

PQL = Practical Quantitation Limit



IEA
An Aquarion Company

CLIENT: E & E
CLIENT ID: EXTRACTION BLANK
LAB ID: FLUID #1

TCLP ANALYTICAL RESULTS

EPA WASTE #	CONTAMINANT/	DATE LEACH:06/01/94	DATE ANALY	REG LIMIT (mg/L)	DETECTION LIMIT (mg/L)	AMOUNT DETECTED (mg/L)
		DATE EXTRACT:06/02/94				
METALS		METHOD				
D004	Arsenic	6010	06/03/94	5.0	0.1	<0.1
D005	Barium	6010	06/03/94	100.0	0.05	<0.05
D006	Cadmium	6010	06/03/94	1.0	0.005	<0.005
D007	Chromium	6010	06/08/94	5.0	0.01	0.020
D008	Lead	6010	06/03/94	5.0	0.05	<0.05
D009	Mercury	7470	06/06/94	0.2	0.0002	<0.0002
D010	Selenium	6010	06/03/94	1.0	0.1	<0.1
D011	Silver	6010	06/03/94	5.0	0.01	<0.01



IEA
An Aquarion Company

CLIENT: E & E
CLIENT ID: EXTRACTION BLANK
LAB ID: FLUID #2

TCLP ANALYTICAL RESULTS

EPA WASTE #	CONTAMINANT/ DATE LEACH:06/01/94 DATE EXTRACT:06/02/94		DATE ANALY	REG LIMIT (mg/L)	DETECTION LIMIT (mg/L)	AMOUNT DETECTED (mg/L)
	METALS	METHOD				
D004	Arsenic	6010	06/03/94	5.0	0.1	<0.1
D005	Barium	6010	06/03/94	100.0	0.05	<0.05
D006	Cadmium	6010	06/03/94	1.0	0.005	<0.005
D007	Chromium	6010	06/03/94	5.0	0.01	<0.01
D008	Lead	6010	06/03/94	5.0	0.05	<0.05
D009	Mercury	7470	06/09/94	0.2	0.0002	<0.0002
D010	Selenium	6010	06/03/94	1.0	0.1	<0.1
D011	Silver	6010	06/03/94	5.0	0.01	<0.01